

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-24161-00-00
Spot: NWNWSENE Sec/Twnshp/Rge: 29-6S-19W
1400 feet from N Section Line, 1150 feet from E Section Line
Lease Name: BAXTER-MILLER Well #: 29-1
County: ROOKS Total Vertical Depth: 3665 feet

Operator License No.: 32639
Op Name: CORAL PRODUCTION CORPORATION
Address: 1600 STOUT ST STE 1500
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	264		170 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/13/2013 12:00 AM
Plug Co. License No.: 34233 Plug Co. Name: MAVERICK DRILLING LLC
Proposal Rcvd. from: JEREMY Company: MAVERICK DRILLING LLC Phone: (620) 388-6419

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE
Date/Time Plugging Completed: 11/13/2013 10:00 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st plug @3534 w/50 sx
2nd plug @1690 w/25 sx
3rd plug @980 w/100 sx
4th plug @310 w/40 sx
5th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

District: 04

Signed

Ed Schumacher
11/26/13

(TECHNICIAN)

CM

NOV 15 2013

KCC WICHITA

NOV 25 2013

RECEIVED

Form CP-2/3