

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20494-00-00
Spot: NESWSE Sec/Twnshp/Rge: 27-5S-21W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MULDER Well #: 2
County: NORTON Total Vertical Depth: 3699 feet

Operator License No.: 34559
Op Name: WM KS ENERGY RESOURCES LLC
Address: 1001 FANNIN, STE 4000
HOUSTON, TX 77002

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3699 | | 175 SX |
| SURF | 8.625 | 222 | | 160 SX |
| T1 | 2.875 | 3600 | | |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2013 11:00 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: TOM BERENS Company: WMKS Phone: (785) 639-5727

| | |
|----------|-----------------------------------------------------------------------|
| Proposed | Ordered 350 sx 60/40 pozmix 4% gel cement, 500 # hulls and 14 sx gel. |
| Plugging | DV tool at 1826' w/450 sx cement. |
| Method: | GPS: 39.58480 -099.67129 |

Plugging Proposal Received By: PAT STAAB WitnessType: NONE
Date/Time Plugging Completed: 11/14/2013 11:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Ran in hole with tubing to 3491' and pumped 14 sx gel followed by 50 sx cement w/300 # hulls. Pulled to 1808' and pumped 180 sx cement w/200 # hulls to circulate cement to surface. Pulled tubing. Topped off 5 1/2" casing w/15 sx cement. Rigged to 8 5/8" casing and pumped 7 sx cement to pressure with 200 psi and 200 psi shut in pressure.

Perfs:

| Top | Bot | Thru | Comments |
|------|-----|------|----------|
| 3626 | | | |

Remarks: ALLIED CEMENTING TICKET # 56822

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN) CM

NOV 20 2013

KCC WICHITA
NOV 25 2013
RECEIVED

Form CP-2/3