

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20498-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 27-5S-21W
1650 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SCHNEIDER Well #: 2
County: NORTON Total Vertical Depth: 3718 feet

Operator License No.: 34559
Op Name: WM KS ENERGY RESOURCES LLC
Address: 1001 FANNIN, STE 4000
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3718		175 SX
SURF	8.625	222		160 SX
T1	2.875	3625		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/15/2013 10:00 AM
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE
Proposal Rcvd. from: TOM BERENS Company: WMKS Phone: (785) 639-5727

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 14 sx gel and 500 # hulls.
DV Tool at 1781' w/500 Sx cement.
PBTB-3717'
GPS: 39.58648 -099.67396

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2013 3:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Western Well Service ran in hole with tubing to 3497'. Rigged to tubing and mixed and pumped 14 sx gel followed by 50 sx cement w/150 # hulls mixed in. Pulled tubing to 1842'. Allied rigged to tubing and mixed and pumped 200 sx cement w/350 # hulls mixed in to circulate cement to surface. Pulled tubing. Topped off 5 1/2" casing with 30 sx cement. Hole standing full. Rigged to 8 5/8" casing and pumped 15 sx cement to pressure w/400 psi and 400 psi shut in pressure

Perfs:


Top	Bot	Thru	Comments
3651			

Remarks: ALLIED CEMENTING TICKET # 54829

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

KCC WICHITA

CM

NOV 20 2013

NOV 25 2013

RECEIVED

Form CP-2/3