

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-03383-00-00
Spot: SESENESEW Sec/Twnshp/Rge: 23-26S-18E
3700 feet from N Section Line, 2450 feet from W Section Line
Lease Name: HARNER Well #: J-36
County: ALLEN Total Vertical Depth: 840 feet

Operator License No.: 5491
Op Name: W & W PRODUCTION COMPANY, GEN
Address: 1150 HWY 39
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	0		0 SX
SURF	8	0		0 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/13/2013 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: MIKE WIMSETT Company: Phone: (620) 431-4137

Proposed Plugging Method: Run 1" inside 2" to TD 840' & circulate cement to 0. Run 1" outside of 2" to TD 840' & circulate cement to 0. No Pit.

Plugging Proposal Received By: RYAN DULING WitnessType: NONE
Date/Time Plugging Completed: 02/13/2013 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2" casing to TD. Ran 1" pipe down the outside of the 2" casing inside the 8" surface casing to 710'. Circulated cement through the 1" pipe inside the 2" casing from TD to surface. Pulled the 1" pipe out of the 2" casing. Circulated cement through the 1" pipe inside the 8" surface casing from 710' to surface. Pulled the 1" pipe. Topped the well off with cement. A total of 151 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED

OCT 30 2013

KCC Chanute Dist. #3

RD

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)

KCC WICHITA Form CP-2/3

NOV 01 2013

RECEIVED