

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02926-00-00
Spot: NESWSW Sec/Twnshp/Rge: 22-9S-21W
990 feet from S Section Line, 4290 feet from E Section Line
Lease Name: SUTOR Well #: 4
County: GRAHAM Total Vertical Depth: 3816 feet

Operator License No.: 8942
Op Name: V & F OIL COMPANY, A GENERAL PAR
Address: 506 W 21ST ST.
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3806 | | 100 SX |
| SURF | 8.625 | 305 | | 150 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/30/2013 12:00 AM
Plug Co. License No.: 34410 Plug Co. Name: AMERICAN PULLING SERVICE
Proposal Rcvd. from: MELISSA SELTMANN Company: AMERICAN PULLING SERVICE Phone: (785) 656-2213

Proposed Plugging Method: Ordered 200 sx 60/40 pozmix 4% gel cement.
Ran three drill collars and tubing with new tri cone drill bit in casing. Tagged cement at 247' and drilled for 13 hours into hard cement to 280'. Stopped and re-plugged well.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/30/2013 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 280' and pumped 35 sx cement. Circulated cement to surface. Pulled tubing out and topped off with 10 sx cement. Tied on to casing and shut in at 300 psi. Tied on to back side and pumped 120 sx cement. Shut in pressure 275 psi.

GPS: 39.25177 -099.65780

Remarks: QUALITY WELL CEMENTING TICKET # 5952

Plugged through: TBG

District: 04

Signed [Signature]
10/20/13 (TECHNICIAN)

CM

OCT 09 2013

Form CP-2/3

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 15 2013
CONSERVATION DIVISION
WICHITA, KS