

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-03166-00-00
Spot: SESENWSE Sec/Twnshp/Rge: 29-26S-20E
1610 feet from S Section Line, 1610 feet from E Section Line
Lease Name: CAMPBELL Well #: C 15
County: ALLEN Total Vertical Depth: 865 feet

Operator License No.: 4485
Op Name: VERDE OIL COMPANY
Address: 1020 NE LOOP 410 STE 555
SAN ANTONIO, TX 78209

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	860		125 SX
SURF	8.625	22		8 SX

Well Type: EOR UIC Docket No: E18163.11 Date/Time to Plug: 09/26/2013 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: JEFF DALE Company: Phone: (620) 754-3800

Proposed Plugging Method: Run tubing to PBSD. Circulate cement to surface. Pull tubing. Fill displacement from surface. Well will be plugged from PBSD to surface.

Plugging Proposal Received By: RYAN DULING WitnessType: PARTIAL
Date/Time Plugging Completed: 09/26/2013 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe to TD. Mixed and pumped gel down the 1" pipe. Pumped 30 sacks of portland cement through the 1" pipe at TD. Pulled 1" pipe up to 500'. Pumped 30 sacks of portland cement at 500'. Pulled 1" pipe up to 250'. Pumped and circulated cement from 250' to surface. Pulled rest of the 1" pipe out of the hole. Topped well off with cement. A total of 166 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
821	830		

RECEIVED
OCT 29 2013
KCC Conate Dist. #3
RD

Remarks:

Plugged through: TBG

District: 03

Signed

[Handwritten Signature]
(TECHNICIAN)
OCT 29 11/06/13
11/22/13

KCC WICHITA

OCT 31 2013

RECEIVED