

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03651-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 33-10S-20W
1650 feet from S Section Line, 2310 feet from E Section Line
Lease Name: TRICO LKC ARBUCKLE UNIT Well #: 303
County: ROOKS Total Vertical Depth: 3740 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3718		100 SX
SURF	8.625	214		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/08/2013 12:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORP. Phone: (785) 483-9169

Proposed Old squeeze: 1040' and 1958' CWC.
Plugging Arbuckle Open Hole: 3718' - 3721'
Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/700# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/08/2013 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3495'. Allied pumped 100 sx cement w/500 # hulls. Pulled tubing to 2400'. Allied pumped 100 sx cement w/200 # hulls. Pulled tubing to 1400'. Allied pumped 135 sx cement. Cement circulated. PTOH. Topped 5 1/2" casing off w/20 sx cement. Casing full. Hooked up to backside and pumped 10 sx cement. Shut in pressure 200 psi.

Perfs:

Top	Bot	Thru	Comments
3718	3740		OH
3546	3624		

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 15 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING TICKET # 54885. LEASE RE-NAMED TRICO LKC ARB UNIT #303-FORMERLY KNOWN AS VEATCH #3.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

OCT 09 2013