

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20276-00-02
Spot: SESESW Sec/Twnshp/Rge: 18-9S-19W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BUCKS Well #: 1
County: ROOKS Total Vertical Depth: 1285 feet

Operator License No.: 31171
Op Name: CONTINENTAL OPERATING CO.
Address: 1221 MCKINNEY STE 3700
HOUSTON, TX 77010

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3545	1200	
SURF	8.625	206		

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 10/31/2013 8:00 AM
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC
Proposal Rcvd. from: RALPH BRUNGARDT Company: CONTINENTAL OPERATING Phone: (785) 628-1966

Proposed Plugging Method:	Lost Hole. RTD 1285' out of hole. Ordered 500 sx 60/40 pozmix 4% gel cement w/400 # hulls.
---------------------------	---

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2013 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

<p>Ran tubing to 1254'. SOS pumped 150 sx cement w/200 # hulls. Pulled tubing to 950' and pumped 150 sx cement w/200 # hulls. Pulled tubing to 600' and pumped 150 sx cement. Cement circulated. POOH. 8 5/8" surface casing full of cement.</p>
--

Perfs:

Remarks: SOS
Plugged through: TBG

KCC WICHITA
NOV 07 2013
RECEIVED

District: 04

Signed Richard Williams (TECHNICIAN) CM
11/19/13