

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-093-00228-00-00  
Spot: SE Sec/Twnshp/Rge: 15-22S-35W  
1328 feet from S Section Line, 1291 feet from E Section Line  
Lease Name: ROONEY Well #: 1  
County: KEARNY Total Vertical Depth: 2728 feet

Operator License No.: 32864  
Op Name: XTO ENERGY INC.  
Address: 210 PARK AVE STE 2350  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2477		WITH 5 SX CMT
PROD	7	2542	0	WITH 900 SX CMT
SURF	10.75	311		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/04/2013 10:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: ALAN Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: Set CIBP @ +/- 2477'. Circ hole w/ 9.0 ppg mud & cap CIBP w/ 5 sks cement. Pull up to 2070' & spot 30 sks cement plug to cover Anhydrite formation. Pull up to 500' & pump 85 sks cement & circulate to surface (BTW @ 450). Top out w/ 5 sks cement. Fill 10 3/4" x 7" annulus with 5 - 15 sks cement. Weld on ID plate. & restore location.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/04/2013 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2477' WITH 5 SX CMT. 1ST PLUG AT 2070' WITH 30 SX CMT. 2ND PLUG FROM 1000' TO 0' WITH 170 SX CMT. FULL CIRCULATION. TOOH W/TBG. TOP OFF WITH 5 SX CMT. PUMP 15 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
2542	2728		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG


KCC WICHITA

SEP 12 2013

RECEIVED

District: 01

Signed



(TECHNICIAN)

RECEIVED

SEP 10 2013

KCC DODGE CITY

ROY