

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-193-20901-00-00  
Spot: NWENWSE Sec/Twnshp/Rge: 28-9S-31W  
2575 feet from S Section Line, 1805 feet from E Section Line  
Lease Name: BIXENMAN Well #: 1-28  
County: THOMAS Total Vertical Depth: 4710 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 1019  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	308		225 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/08/2013 12:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: Ordered 220 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: NONE  
Date/Time Plugging Completed: 10/08/2013 6:45 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

1st plug @2660 w/25 sx  
2nd plug @1800 w/100 sx  
3rd plug @360 w/40 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

KCC WICHITA  
NOV 07 2013  
RECEIVED

District: 04

Signed Darrel Dipman  
10/19/13 (TECHNICIAN)

CM

OCT 25 2013