

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20476-00-01
Spot: SENWSWSW Sec/Twnshp/Rge: 22-1S-32W
667 feet from S Section Line, 4664 feet from E Section Line
Lease Name: REUBER Well #: 5
County: RAWLINS Total Vertical Depth: 4127 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|--|
| PKR | | 3900 | | PACKER TYPE AND SETTING DEPTH: BAKER TENSION SET @ 3900' |
| PROD | 5.5 | 4126 | | 150 SX |
| SURF | 8.625 | 301 | | 185 SX |
| T1 | 2.375 | 3900 | | |

Well Type: EOR UIC Docket No: E27159.3 Date/Time to Plug: 10/29/2013 11:00 AM
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-3144

Proposed Plugging Method: 8 5/8" surface casing set at 301' w/185 sx cement. 5 1/2" production casing set at 4126' w/150 sx cement. DV Tool set at 2787' w/375 sx cement. TD 4127', PBSD at 4101'. Perforations: 3972' - 4083'.
Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 7 sx gel and 600 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/29/2013 2:50 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Allied Cement Company brought out 450 sx cement, 4 sx gel and 600 # hulls. Altered plugging plan due to lack of gel. Ran tubing to 4000' and pumped 4 sx gel followed by 80 sx cement w/250 # hulls. Pulled tubing to 2740' and pumped 130 sx cement w/200 # hulls. Pulled tubing to 1400' and pumped 120 sx cement w/150 # hulls. Cement circulated to surface. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 20 sx cement. Connected to 8 5/8" surface casing and pumped 20 sx cement. Maximum pressure 150 psi. Casing ruptured.
GPS: 39.94599N -100.90461W

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4080 | 4083 | | |
| 3972 | 3980 | | |

Remarks: ALLIED CEMENT COMPANY TICKET # 61404

KCC WICHITA
NOV 27 2013

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

RECEIVED

CM

NOV 04 2013

cc to UIC 11/27/13
11/27/13