

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22777-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 3-7S-20W
2310 feet from N Section Line, 2970 feet from W Section Line
Lease Name: GARY L STATES Well #: 32-3-1
County: ROOKS Total Vertical Depth: 3720 feet

Operator License No.: 31100
Op Name: ROBUCK PETROLEUM., LLC
Address: PO BOX 1896
EDWARDS, CO 81632

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3719		605 SX
SURF	8.625	274		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/25/2013 3:00 PM
Plug Co. License No.: 31100 Plug Co. Name: ROBUCK PETROLEUM., LLC
Proposal Rcvd. from: BRETT ROBUCK Company: ROBUCK PETROLEUM., LLC Phone: (308) 345-7200

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/300 # hulls.
Production perforations at 3396' - 3402', 3430' - 3434', 3543' - 3548', 3583' - 3587', 3590' - 3593', 3633' - 3637' and 3641' - 3647'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/25/2013 6:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3344' and pumped 150 sx cement w/200 # hulls. Pulled tubing to 2212' and pumped 125 sx cement w/100 # hulls. Pulled tubing to 1116' and pumped 90 sx cement to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing w/10 sx cement. Shut in pressure 270 psi.

GPS: 39.47469N -099.3637W

Perfs:

Top	Bot	Thru	Comments
3641	3647		
3633	3637		
3590	3593		
3583	3587		
3558	3565		
3543	3548		
3430	3434		
3396	3402		

KCC WICHITA

Remarks: SOS TICKET # 1142

NOV 27 2013

Plugged through: TBG

RECEIVED

District: 04

Signed

Pat Bedore
11/27/13 (TECHNICIAN)

CM

NOV 06 2013