

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24757-00-00  
Spot: SWSESE Sec/Twnshp/Rge: 20-20S-14W  
330 feet from S Section Line, 990 feet from E Section Line  
Lease Name: BROZEK Well #: 1-20  
County: BARTON Total Vertical Depth: 3750 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5600		
PROD	5.5	3746		100 SX
SURF	8.625	892		335 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/14/2013 8:00 AM  
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.  
Proposal Rcvd. from: ROB LONG Company: F G HOLL Phone: (620) 793-0915

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls and 18 sx gel.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/14/2013 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400' and 870'. Ran tubing to 3620' and pumped 18 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1450' and pumped 60 sx cement w/100 # hulls. Pulled tubing to 870'. Circulated cement to surface on casing and surface pipe with 260 sx cement and 200 # hulls. Pulled tubing. Topped off w/10 sx cement.

GPS: 38.29085 -098.88812

Perfs:

Top	Bot	Thru	Comments
3616	3620		BSPF
3610	3613		SPF
3609	3612		BSPF
3606	3607		SPF
3605	3620		SPF

Remarks: ALLIED CEMENTING

Plugged through: TS6  
ES6

District: 04

Signed Bruce Rodie (TECHNICIAN) 10/19/13 CM

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3

OCT 16 2013

OCT 23 2013

CONSERVATION DIVISION  
WICHITA, KS