

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22817-00-00
Spot: NESWNE Sec/Twnshp/Rge: 3-7S-20W
1650 feet from N Section Line, 3630 feet from W Section Line
Lease Name: GARY L STATES Well #: 32-3-2
County: ROOKS Total Vertical Depth: 3775 feet

Operator License No.: 31100
Op Name: ROBUCK PETROLEUM., LLC
Address: PO BOX 1896
EDWARDS, CO 81632

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3724		665 SX
SURF	8.625	303		315 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/24/2013 1:00 PM
Plug Co. License No.: 31100 Plug Co. Name: ROBUCK PETROLEUM., LLC
Proposal Rcvd. from: BRETT ROBUCK Company: ROBUCK PETROLEUM., LLC Phone: (308) 345-7200

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 6 sx gel and 300 # hulls.
Production perforations at 3538' - 3544', 3552' - 3559' and 3578' - 3584'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/24/2013 5:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3439' and pumped 6 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 2212' and pumped 125 sx cement w/100 # hulls. Pulled tubing to 1116' and pumped 110 sx cement to circulate cement to surface. Pulled all tubing and topped off 4 1/2" casing w/20 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 20 sx cement. Shut in pressure 360 psi.

GPS: 39.47652N -099.53408W

Perfs:

Top	Bot	Thru	Comments
3578	3584		
3552	3559		
3538	3544		

Remarks: SOS TICKET # 1140

Plugged through: TBG

District: 04

Signed

Pat Bedore
10/24/13 (TECHNICIAN)

CM

NOV 06 2013

KCC WICHITA Form CP-2/3

NOV 27 2013

RECEIVED