

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22094-00-00
Spot: W2SE Sec/Twnshp/Rge: 15-14S-12W
1320 feet from S Section Line, 1980 feet from E Section Line
Lease Name: BEISEL Well #: 7
County: RUSSELL Total Vertical Depth: 3264 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3263		100 SX
SURF	8.625	670		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/28/2013 8:30 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/300 # hulls.
Perforation: 1250'

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/28/2013 3:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Bottom of well plugged with iron sulfide, scale, etc. Ran tubing to 2488' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1760' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1000' and pumped 65 sx cement. Cement circulated out backside. POOH. Hooked to casing and pumped 170 sx cement. Cement circulated out braden head. Shut in braden head and pumped 15 sx cement to pressure to 300 psi. Shut in.

GPS: 38.83109 -098.63925

Perfs:

Top	Bot	Thru	Comments
3263	3264		

KCC WICHITA

Remarks: ALLIED CEMENTING TICKET # 54737

Plugged through: TBG

NOV 07 2013
RECEIVED

District: 04

Signed Ray Dinkel
W 28/13 (TECHNICIAN)

CM

OCT 29 2013