

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-141-20128-00-00
Spot: SESWSW Sec/Twnshp/Rge: 3-10S-15W
330 feet from S Section Line, 990 feet from W Section Line
Lease Name: HOBROCK Well #: 4
County: OSBORNE Total Vertical Depth: 3645 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3644		175 SX
SURF	8.625	236		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/11/2012 8:00 AM
Plug Co. License No.: 32278 Plug Co. Name: TENGASCO, INC.
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed	Backside squeezed w/275 sx.
Plugging	Production perforations: 3198' - 3400'.
Method:	CIBP at 3560' Ordered 275 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 11/11/2013 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3300'. Allied pumped 125 sx cement w/300 # hulls. Pulled tubing to 1600' and pumped 115 sx w/200 # hulls. Cement circulated. PTOH. Topped 4 1/2" casing off w/20 sx cement. Hooked up to backside and pumped 7 sx cement. Shut in pressure 200 psi.

Perfs:

Top	Bot	Thru	Comments
3607	3611		
3239	3400		
3198	3201		

Remarks: ALLIED TICKET # 056818
Plugged through: TBG

KCC WICHITA
NOV 19 2013
RECEIVED

District: 04

Signed Richard Williams
11/29/13 (TECHNICIAN)

NOV 12 2013