

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22324-00-00
Spot: SWNESE Sec/Twnshp/Rge: 28-16S-29W
2283 feet from S Section Line, 398 feet from E Section Line
Lease Name: JASPER Well #: 1
County: LANE Total Vertical Depth: 4600 feet

Operator License No.: 34392
Op Name: TEXKAN EXPLORATION LLC
Address: 307 NW 3RD ST PO BOX H
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		2236		WITH 500 SX CMT
PROD	5.5	4598	0	WITH 150 SX CMT
SURF	8.625	241		WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/01/2013 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TOM BERENS Company: TEXKAN Phone: (785) 688-4040

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP GEL SPACER, THEN 35 SX CMT & 150# HULLS. PULL TBG TO 2236' & CIRCULATE CMT. PULL TBG & TOP OFF. THEN TIED ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/04/2013 9:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4508' & PUMPED 20 SX GEL, FOLLOWED BY 35 SX CMT & 150# HULLS. PULLED TBG TO 2217' & PUMPED 100 SX CMT & 350# HULLS. CMT WAS ON A VACUUM. PULLED TBG TO 1021' & MIXED 165 SX CMT. DID NOT CIRCULATE. TIED ONTO BACKSIDE & PRESSURED UP TO 500# RIGHT AWAY. SDFW. 11/4/13: RUN IN WITH SAND LINE AND TAGGED CMT AT 1900'. RUN TBG TO 1200' & MIXED 130 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4531	4535		
4524	4527		

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

NOV 27 2013

Plugged through: TBG

RECEIVED

District: 01

Signed Michael J Maier
11/27/13 (TECHNICIAN)

RECEIVED

NOV 20 2013

KCC DODGE CITY