

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-20478-00-00  
Spot: SENESWNW Sec/Twnshp/Rge: 2-22S-19E  
3310 feet from S Section Line, 3966 feet from E Section Line  
Lease Name: UNIT 3 Well #: RW-25  
County: ANDERSON Total Vertical Depth: 860 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	850		115 SX
SURF	7	14		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/16/2013 12:00 AM  
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.  
Proposal Rcvd. from: STERLING BARKER Company: \_\_\_\_\_ Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Tie on to tubing and squeeze untill desired amount and pressure are achieved. dig out 3' below ground and cut,cap and backfill.

Plugging Proposal Received By: FORREST SUTHERLAND WitnessType: NONE  
Date/Time Plugging Completed: 05/16/2013 12:00 AM KCC Agent: FORREST SUTHERLAND

Actual Plugging Report:

RAN WORKSTRING TO BOTTOM, CEMENTED TO SURFACE. PULLED WORKSTRING OUT AND TOPPED WELL OFF WITH CEMENT. TIED ONTO WELL AND SQUEEZED CEMENT UNTIL DESIRED AMOUNT OF PRESSURE WAS ACHIEVED. SHUT WELL IN AT 500#. 30 SACKS USED.

Perfs:

Top	Bot	Thru	Comments
836	843		

RECEIVED  
OCT 30 2013  
KCC Chanute Dist. #3  
FS

Remarks:

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)

KCC WICHITA

Form CP-2/3

NOV 01 2013

RECEIVED