

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-069-20449-00-00  
Spot: SWSWSWNW Sec/Twnshp/Rge: 19-27S-29W  
2649 feet from S Section Line, 257 feet from W Section Line  
Lease Name: RPM FARMS Well #: 1-19  
County: GRAY Total Vertical Depth: 5240 feet

Operator License No.: 34472  
Op Name: SUNFLOWER ENERGY, LLC  
Address: 10801 MASTIN, STE 920  
OVERLAND PARK, KS 66210

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1852		WITH 600 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/14/2013 10:00 AM  
Plug Co. License No.: 34127 Plug Co. Name: TOMCAT DRILLING LLC  
Proposal Rcvd. from: DAVID RICE Company: CROWN CONSULTING Phone: \_\_\_\_\_

Proposed Plugging Method: 1ST PLUG AT 1890' WITH 50 SX CMT. 2ND PLUG AT 870' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE  
Date/Time Plugging Completed: 11/14/2013 12:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

1ST PLUG AT 1890' WITH 50 SX CMT. 2ND PLUG AT 870' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

Signed

*[Handwritten Signature]*  
11/26/13

(TECHNICIAN)

RECEIVED

NOV 20 2013

KCC DODGE CITY

KCC WICHITA

Form CP-2/3

NOV 25 2013

RECEIVED

*AAW*