

9-27

1 040169

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,670-00-00

NE NE SE, SEC. 24, T 31 S, R 15 W/E

2310 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Hull "B" Well # 1

Operator: TXO Production Corporation

County Barber 158.44

Name & Address 155 North Market, Suite 1000

Well Total Depth 4875 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:45 p.m. Day: 27 Month: 9 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 2 7/8" at 4874' PBD 4834' Perfs at 4633-35' Elevation 1821'GL

1st plug pump 10 sx common cement to bottom.

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

OCT 5-1988

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations Abandoned by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 p.m. Day: 27 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped down 2 7/8" casing with 10 sx of common cement.

Pumping pressure 2500 psi. Stopped plug at 4000'.

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls. released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 650 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2800' of 2 7/8" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 10-10-88

Signed Stephen J. Pfeifer
(TECHNICIAN)

INV. NO. 22551