

To: 1 040600
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-11
API NUMBER 15- 007-21,470-00-00 95 R
C SE NE, SEC. 4, T. 31 S, R. 15 W&E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5298

Operator: Gould Oil, Inc.
Name & Address 110 N. Market, Suite 411
Wichita, KS 67202

3300 feet from S section line
660 feet from E section line

Lease Name Lenkner Well # C-1

County Barber 148.52

Well Total Depth 4570 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 347, Pratt, KS 67124-0847

Company to plug at: Hour: 1:30 p.m. Day: 11 Month: 12 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 4 1/2" at 4563' w/175 sx cement, PBTD 4250', Perfs at 3099-3101'

1st plug sand back to 3040' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 p.m. Day: 11 Month: 12 Year: 19 91

ACTUAL PLUGGING REPORT Had sanded hole back from 4250-3500' prior to setting CIBP.

1st plug set CIBP at 3000' and pump 2 sx cement on top of CIBP through dump bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1893' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

(VOID / XEROX) observe this plugging.

DATE 1-7-92

INV. NO. 34213

Signed Stephen J. Pfeiffer
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS
12-18-91
12-18-91