

1050476

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,009-00-00
150' N & 100' W OF E/2 SE/4, SEC. 4, T 31 S, R 15 W/EX

1470 feet from S section line
760 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Lease Name Lenkner Well # 1 (Twin)

Operator: Abercrombie Drilling, Inc.
Name & Address: 801 Union Center
Wichita, KS 67202

County Barber 149.50

Well Total Depth 4600 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 852

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 5:00 pm Day: 1 Month: March Year: 19 85

Plugging proposal received from Wilbur Dreiling

(company name) Abercrombie (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 900' with 40 sx cement

2nd plug at 450' with 30 sx cement

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

RECEIVED
STATE CORPORATION COMMISSION
MAR 15 1985
3-15-85
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:45 pm Day: 1 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 900' with 40 sx cement, 2nd plug at 450' with 30 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Buie

If additional description is necessary, use BACK of this form.)

INVOICED

(If possible, please observe this plugging.)

DATE 3-18-85

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 7354

APR 9 1985