

1 030375

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-22,001-00-00
150' N C
E/2 SE/4, SEC. 4, T 31 S, R 15 W/K
1470 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Lease Name Lenkner Well # 1

Operator: Abercrombie Drilling, Inc.

County Barber 82.65

Name & Address 801 Union Center

Well Total Depth 2543 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 11:30 pm Day: 14 Month: February Year: 19 85

Plugging proposal received from Wemp Dreiling

(company name) Abercrombie (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1110' with 50 sx cement

RECEIVED
STATE CORPORATION COMMISSION

2nd plug at 720' with 50 sx cement

3rd plug at 330' with 50 sx cement

FEB 25 1985
2-25-85

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

CONSERVATION DIVISION
Wichita, Kansas

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 6:00 am Day: 15 Month: February Year: 19 85

ACTUAL PLUGGING REPORT loss of circulation at 630-650' Static fluid level at 270'

We set plugs 1 & 2 as ordered. Attempted to bridge bottom of surface pipe at 300' with 6 sx hull sacks and rubber plug and 6 more sacks and 2 plugs. Would hold weight of 4 drill collars and drill pipe. Loaded hole with fluid and plugs fell out of surface pipe. Since fluid level was at 270' we pumped 50 sx cement at 300'. Tagged plug two hours later. O.K. Finished plugging well by circulating cement at 60' to surface with 15 sx

cement. Remarks: Used 60/40 Pozmix 2% gel 3% cc by Buie

(additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 2-27-85

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 7160
2-15

MAR 15 1985

MAY 02 1985