

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-25126-00-01  
Spot: SW Sec/Twnshp/Rge: 30-26S-17E  
495 feet from S Section Line, 3795 feet from E Section Line  
Lease Name: NELSON D Well #: 19  
County: WOODSON Total Vertical Depth: 870 feet

Operator License No.: 31652  
Op Name: NORSTAR PETROLEUM, INC.  
Address: 88 INVERNESS CIR E. UNIT F104  
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	870		

Well Type: EOR UIC Docket No: E26404.4 Date/Time to Plug: 11/18/2012 12:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: Run 1" pipe to TD. Circulate cement from TD to surface.

Plugging Proposal Received By: RYAN DULING WitnessType: NONE  
Date/Time Plugging Completed: 11/18/2012 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Washed down the inside of the 2.875" casing to TD with 1" pipe. Pumped cement through the 1" pipe inside the 2.875" casing at TD. Pulled 1" pipe up to 400'. Circulated cement from 400' to surface. Pulled 1" pipe to 200'. Circulated cement from 200' to surface. Pulled the rest of the 1" pipe out of the hole. Topped well off with cement. A total of 35 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED  
OCT 29 2013  
KCC Chanute Dist. #3  
RD

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature] (TECHNICIAN)

\* SEE NOTATION BELOW \*

cc to UIC 11/21/13

KCC WICHITA

Form CP-2/3

Approved by NT to COLT  
ENERGY INV. # 2014060556 in error. Corrected INV. on 11/27/13.  
New INV. #: 2014060617, INV. dt.: 11/27/13

OCT 31 2013

RECEIVED

[Signature]