

1 050507

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,084-00-00

NE NW SW , SEC. 6 , T 16 S, R 18 W/E  
2310 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050  
(formerly owned by Sunburst)  
Operator: Kelso Casing Pulling  
Name & Address P. O. Box 347  
Chase, KS 67524

Lease Name Bieker Well # 1  
County Rush 117.20  
Well Total Depth 3606 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 1182

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Box 347, Chase, KS 67524

Company to plug at: Hour: noon Day: 24 Month: April Year: 19 85

Plugging proposal received from Millard Kelso  
(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 3595' PBTD 3545' Perfs at 3481

1st plug sand back to 3430' and dump 4 sx cement on top of sand through bailer  
2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, release 8 5/8" rubber  
plug and pump 125 sx cement.

Plugging Proposal Received by Robert B. Tarbutton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:30 pm Day: 24 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3430' and dumped 4 sx cement on top of  
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement,  
released 8 5/8" rubber plug and pumped an additional 125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 02 1985  
S-2-85

CONSERVATION DIVISION  
Wichita, Kansas

Maximum pressure 800 psi and shut in 300 psi

Remarks: Recovered 2300' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-7-85

INV. NO. 8014

Signed Richard W. Lacey  
(TECHNICIAN)