

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24767-00-00
Spot: SWNESESW Sec/Twnshp/Rge: 32-17S-14W
880 feet from S Section Line, 2300 feet from W Section Line
Lease Name: SCHNEIDER Well #: 1-32
County: BARTON Total Vertical Depth: 3468 feet

Operator License No.: 31504
Op Name: STRUBE, KURT J. DBA K.J.S. OIL
Address: 608 W PARK ST
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3466	1758	150 SX
SURF	8.625	385		
T1	2.375	3414		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/30/2012 12:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: KURT J STRUBE Company: K J S OIL Phone: (620) 793-2046

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/30/2012 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with 3 sx cement. Cut casing at 1861'. Pulled casing to 1450' and pumped 135 sx cement w/100 # hulls. Pulled casing to 950' and pumped 25 sx cement w/100 # hulls. Pulled casing to 385'. Circulated cement w/85 sx cement. Pulled casing. Hole stayed full.

GPS: 38.52361 -098.89605

Perfs:

Top	Bot	Thru	Comments
3351	3353		
3279	3281		
3206	3208		
3194	3196		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

KCC WICHITA Form CP-2/3

NOV 25 2013

RECEIVED

NOV 06 2013