

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-21115-00-00
Spot: SESENWNW Sec/Twnshp/Rge: 10-22S-19E
4060 feet from S Section Line, 4220 feet from E Section Line
Lease Name: A W BRECHEISEN Well #: 27
County: ANDERSON Total Vertical Depth: 820 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.5	818		0 SX
SURF	7	22		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/25/2013 12:00 AM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Rcvd. from: STERLING BARKER Company: _____ Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string out and top well off with cement. Tie onto tubing and squeeze cement until desired amount of pressure is achieved. Cut off well 3' below surface.

Plugging Proposal Received By: FORREST SUTHERLAND WitnessType: NONE
Date/Time Plugging Completed: 07/03/2013 12:00 AM KCC Agent: FORREST SUTHERLAND

Actual Plugging Report:

TIED ONTO TUBING AND SQUEEZED CEMENT UNTIL PRESSURE STARTED TO CLIMB. INSERTED CEMENT PLUG INTO TUBING AND PUMPED DOWN TO 750'. BOND LOGGED WELL. RAN WORKSTRING TO 750' AND PUMPED CEMENT TO SURFACE. PULLED WORKSTRING OUT AND TOPPED WELL OFF WITH CEMENT. 65 SACKS USED TO PLUG WELL.

Perfs:

Top	Bot	Thru	Comments
793	803		

RECEIVED
OCT 30 2013
KCC Chanute Dist. #3
FS

Remarks:
Plugged through: TBG

District: 03

Signed _____ (TECHNICIAN)
M/26/13

KCC WICHITA Form CP-2/3
NOV 01 2013
RECEIVED