

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20928-00-00
Spot: NENWSESE Sec/Twnshp/Rge: 9-22S-19E
1180 feet from S Section Line, 800 feet from E Section Line
Lease Name: BABCOCK Well #: 2
County: ANDERSON Total Vertical Depth: 882 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.5	882		0 SX
SURF	7	25		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/19/2013 12:00 AM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Rcvd. from: STERLING BARKER Company: _____ Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string out and top well off with cement. Tie onto tubing and squeeze cement until desired amount of pressure is achieved. Cut off well 3' below surface.

Plugging Proposal Received By: FORREST SUTHERLAND Witness Type: NONE
Date/Time Plugging Completed: 08/20/2013 12:00 AM KCC Agent: FORREST SUTHERLAND

Actual Plugging Report:

TIED ONTO TUBING AND SQUEEZED CEMENT UNTIL PRESSURE STARTED TO CLIMB. INSERTED RUBBER CEMENT PLUG AND PUMPED IT DOWN TO 800'. 8/20/13- BOND LOGGED WELL. RAN WORKSTRING DOWN TO 800' AND PUMPED CEMENT TO SURFACE. PULLED WORKSTRING OUT AND TOPPED WELL OFF WITH CEMENT. 77 SACKS USED TO PLUG WELL.

Perfs:


Top	Bot	Thru	Comments
858	868		

RECEIVED
OCT 30 2013
KCC Chanute Dist. #3
FS

Remarks:

Plugged through: TBG

District: 03

Signed  (TECHNICIAN)
11/26/13

KCC WICHITA

Form CP-2/3

NOV 01 2013

RECEIVED