

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-203-20240-00-00
Spot: SENWNESE Sec/Twnshp/Rge: 11-18S-36W
2070 feet from S Section Line, 930 feet from E Section Line
Lease Name: MCNEIL TRUST Well #: 1-11
County: WICHITA Total Vertical Depth: 5070 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	2222		WITH 200 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/03/2013 2:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KELLY WILSON Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 2460' WITH 50 SX CMT. 2ND PLUG AT 1410' WITH 80 SX CMT. 3RD PLUG AT 720' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 11/03/2013 4:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 2460' WITH 50 SX CMT. 2ND PLUG AT 1410' WITH 80 SX CMT. 3RD PLUG AT 720' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
NOV 20 2013
KCC DODGE CITY

Signed Eric MacLaren
11/26/13 (TECHNICIAN)

KCC WICHITA

NOV 25 2013

RECEIVED

Form CP-2/3

Handwritten initials