

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-22150-00-00
Spot: NWNEENW Sec/Twnshp/Rge: 10-15S-31W
270 feet from N Section Line, 2010 feet from W Section Line
Lease Name: T-NELSON Well #: 1-10
County: GOVE Total Vertical Depth: 4264 feet

Operator License No.: 31120
Op Name: PELICAN HILL OIL & GAS, INC.
Address: 1401 N EL CAMINO REAL SUITE 207
SAN CLEMENTE, CA 92672

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	263		170 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/09/2013 12:00 AM
Plug Co. License No.: 34535 Plug Co. Name: INTEGRITY DRILLING CO., LLC
Proposal Rcvd. from: TODD Company: INTEGRITY DRILLING CO., LLC Phone: (785) 421-7162

Proposed Plugging Method: Ordered 205 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 11/09/2013 7:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @2120 w/25 sx
2nd plug @1175 w/100 sx
3rd plug @300 w/40 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

District: 04

Signed C. Morris
11/26/13 (TECHNICIAN)

NOV 18 2013

KCC WICHITA Form CP-2/3
NOV 25 2013
RECEIVED