

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22354-00-00
Spot: SWNESWNE Sec/Twnshp/Rge: 32-14S-21W
1780 feet from N Section Line, 1850 feet from E Section Line
Lease Name: MAIER SC Well #: 1-32
County: TREGO Total Vertical Depth: 4020 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4019		200 SX
SURF	8.625	215		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/19/2013 8:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE KERNS Company: WHITETAIL CRUDE, INC Phone: (785) 623-3780

Proposed Perforations at 3910' - 3916' and 3918' - 3920'.
Plugging Port Collar at 1440' w/175 sx cement.
Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 19 sx gel and 400 # hulls.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2013 12:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3982' and pumped 19 sx gel followed by 50 sx cement w/300 # hulls. Pulled tubing to 1595' and pumped 210 sx cement. Good circulation of cement. Pulled tubing out. Topped off with 20 sx cement. Hole standing full. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 400 psi.

GPS: 38.79333 -099.67722

Perfs:

Top	Bot	Thru	Comments
3918	3920		
3910	3916		

Remarks: SWIFT CEMENT TICKET # 25794

Plugged through: TBG

District: 04

Signed


11/26/13 (TECHNICIAN)

KCC WICHITA

CM

NOV 20 2013

NOV 25 2013

Form CP-2/3

RECEIVED