

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20440-00-00
Spot: NESE Sec/Twnshp/Rge: 4-35S-30W
1880 feet from S Section Line, 591 feet from E Section Line
Lease Name: ADAMS Well #: 8
County: MEADE Total Vertical Depth: 6320 feet

Operator License No.: 5225
Op Name: QUINQUE OPERATING COMPANY
Address: 908 NW 71ST ST
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	6319	1802	WITH 175 SX CMT
SURF	8.625	1561		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2013 9:00 AM
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.
Proposal Revd. from: PHIL DOLLAR Company: PHIL DOLLAR OILFIELD SERVICE Phone: (806) 435-3373

Proposed Plugging Method: SET CIBP @ 5980' WITH 5 SX CMT. LOAD HOLE WITH MUD. PLUG AT 1600' WITH A 50 SX BALANCED PLUG. PLUG AT 600' WITH 50 SX CMT. PLUG AT 50' TO SURFACE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2013 12:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

BOTTOM PLUG: LOADED THE HOLE WITH 60 BBL MUD, SPOTTED 30 SX CMT WITH 3% CC. 1ST PLUG AT 1611' WITH A 50 SX BALANCED PLUG. 2ND PLUG AT 589' WITH 50 SX CMT. 3RD PLUG AT 58' WITH 40 SX CMT. CMT CIRCULATED & HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
6020	6044		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY PHIL DOLLAR OILFIELD SERVICES.

Plugged through: TBG

District: 01

RECEIVED
NOV 20 2013
KCC DODGE CITY

Signed Eric MacLaren
11/26/13 (TECHNICIAN)

KCC WICHITA

NOV 25 2013

RECEIVED