

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-22726-00-00
Spot: NENWNWSW Sec/Twnshp/Rge: 22-22S-19E
2475 feet from S Section Line, 4785 feet from E Section Line
Lease Name: CLEAVER/TINSLEY Well #: 2
County: ANDERSON Total Vertical Depth: 880 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	878		0 SX
SURF	6	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/01/2013 12:00 AM
Plug Co. License No.: 6372 Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.
Proposal Rcvd. from: STERLING BARKER Company: _____ Phone: (785) 448-4816

Proposed Plugging Method: Run workstring to TD, cement to surface, tie to 2.875" squeeze untill desired pressure and volume is achieved. Dig out, cut and cap 3' below surface.

Plugging Proposal Received By: FORREST SUTHERLAND WitnessType: NONE
Date/Time Plugging Completed: 07/10/2013 12:00 AM KCC Agent: FORREST SUTHERLAND

Actual Plugging Report:

TIED ONTO WELL AND SQUEEZED CEMENT UNTIL PRESSURE STARTED TO CLIMB. INSERTED CEMENT PLUG INTO TUBING AND PUSHED DOWN TO 750'. BOND LOGGED WELL. RAN WORKSTRING TO 750' AND PUMPED CEMENT TO SURFACE. PULLED WORKSTRING OUT AND TOPPED WELL OFF WITH CEMENT. 76 SACKS USED TO PLUG WELL.

Perfs:

RECEIVED

OCT 30 2013

KCC Chanute Dist. #3

FS

Remarks:

Plugged through: TBG

District: 03

Signed _____

[Signature]
(TECHNICIAN)

KCC WICHITA

NOV 01 2013

RECEIVED

Form CP-2/3