

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-22531-00-00

Spot: SESWSWNW

Sec/Twnshp/Rge: 22-22S-19E

2860 feet from S Section Line, 4680 feet from E Section Line

Lease Name: COOPER

Well #: 14

County: ANDERSON

Total Vertical Depth: 877 feet

Operator License No.: 33097

Op Name: SOUTHERN STAR CENTRAL GAS PIPE

Address: 4700 HWY 56

OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	876		0 SX
SURF	6.25	20		0 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/28/2013 12:00 AM

Plug Co. License No.: 6372

Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.

Proposal Rcvd. from: STERLING BARKER

Company:

Phone: (785) 448-4816

Proposed Plugging Method: Run workstring to bottom, cement to surface. Pull workstring out and top well off with cement. Tie onto tubing and squeeze cement until desired amount of pressure is achieved. Cut off well 3' below surface.

Plugging Proposal Received By: FORREST SUTHERLAND

WitnessType: NONE

Date/Time Plugging Completed: 07/16/2013 12:00 AM

KCC Agent: FORREST SUTHERLAND

Actual Plugging Report:

TIED ONTO TUBING AND SQUEEZED CEMENT UNTIL PRESSURE STARTED TO CLIMB. INSERTED CEMENT PLUG INTO TUBING AND PUSHED PLUG DOWN TO 750'. BOND LOGGED WELL. RAN WORKSTRING TO 750' PUMPED CEMENT TO SURFACE. PULLED WORKSTRING OUT AND TOPPED WELL OFF WITH CEMENT. 75 SACKS USED TO PLUG WELL.

Perfs:

Top	Bot	Thru	Comments
840	855		
RECEIVED			
OCT 30 2013			
KCC Chanute Dist. #3			
FS			

Remarks:

Plugged through: TBG

District: 03

Signed

11/26/13 (TECHNICIAN)

KCC WICHITA

Form CP-2/3

NOV 01 2013

RECEIVED