

TO:
**STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN**
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-22438-00-00
Spot: S2S2SWNE Sec/Twnshp/Rge: 16-22S-19E
2860 feet from S Section Line, 1980 feet from E Section Line
Lease Name: KOCH NORTH Well #: 8
County: ANDERSON Total Vertical Depth: 825 feet

Operator License No.: 33097

Op Name: SOUTHERN STAR CENTRAL GAS PIPE

**Address: 4700 HWY 56
OWENSBORO, KY 42301**

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.5	823		93 SX
SURF	6.25	20		5 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/27/2013 12:00 AM

Plug Co. License No.: 6372

Plug Co. Name: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.

Proposal Rcvd. from: STERLING BARKER

Company:

Phone: (785) 448-4816

Proposed Run work string to bottom, cement to surface. Pull work string out and top well off with cement. Tie onto tubing and
Plugging squeeze cement until desired amount of pressure is achieved. Cut well off 3' below surface.
Method:

Plugging Proposal Received By: FORREST SUTHERLAND WitnessType: NONE

Date/Time Plugging Completed: 07/08/2013 12:00 AM KCC Agent: FORREST SUTHERLAND

Actual Plugging Report:

TIED ONTO TUBING AND SQUEEZED CEMENT UNTIL PRESSURE STARTED TO CLIMB. INSERTED CEMENT PLUG INTO TUBING AND PUMPED DOWN TO 750'. BOND LOGGED WELL. RAN WORKSTRING TO 750' AND PUMPED CEMENT TO SURFACE. PULLED WORKSTRING OUT AND TOPPED WELL OFF WITH CEMENT. 65 SACKS USED TO PLUG WELL.

Perfs:

Top	Bot	Thru	Comments
807	810		

RECEIVED

OCT 30 2013

KCC Chanute Dist. #3

FS

Remarks:

Plugged through: TBG

District: 03

Signed

(TECHNICIAN)

✓ 10/26/13

KCC WICHITA

Form CP-2/3

NOV 01 2013

RECEIVED