

1 040346

11-1 15-007-20583-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 1/9/78
E/2 NE NW, SEC. 27, T 31 S, R 13 W/E
4620 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name Parr Well # 1

Operator: Beren Corporation

County Barber 138.29

Name: Beren Corporation

Well Total Depth 4255 feet

Address Box 723

Conductor Pipe: Size _____ feet

Hays, KS 67601

Surface Casing: Size 8 5/8 feet 298

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 1 Month: 11 Year: 1989

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 3739.20' Perfs: at 3599-3601, 3592-96, 3596-98, 3601-04' PBTD 3700'

1st plug sand back to 3550' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 1 Month: 11 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded back to 3530' and dumped 5 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement

Maximum pressure 1000 psi and shut in 800 psi.

NOV - 7 1989

Remarks: Used 60/40 Pozmix 6% gel 2% cc 3% gel by B.J. Titan. Recovered 2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
IN (11-1) (11-1) observe this plugging.

DATE 11-13-89

Signed Stephen J. Pfeiffer
(TECHNICIAN)

INV. NO. 26381