

4055-W

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21586-00-00

W/SW1/4SW1/4 Sec. 24, T 31 S, R 13 W1/4

330 feet from 1/4 S section line

2385 feet from 1/4 E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Clark J Well # 2

Operator: TXO Production Corp
Name & Address 200 W. Douglas, Suite 300
Wichita, Kansas 67202

County Barber

Well Total Depth 3750 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 328

121.84

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor FWA Drilling Co Inc License Number 6165

Address P.O. Box 970 Yukon, OK 73099

Company to plug at: Hour: 8:00am Day: 2 Month: April Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Maurice Pounds

(company name) FWA Drilling Co Inc (phone) _____

were: 50/50 pozmix 4% gel 3% cc

1st Plug @ 1560' w/40sx, 2nd Plug @ 780' w/40sx
3rd Plug @ 360' w/40sx 4th Plug @ 40' with a solid Bridge Plug + 10sx Circulate 10sx in both the Rathole + Mousehole

Signed Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2:45 pm Day: 2 Month: April Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered in above paragraph

Remarks: Dowell well did the cement pumping

RECEIVED STATE CORPORATION COMMISSION

APR 07 1983

CONSERVATION DIVISION Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

RECEIVED STATE CORPORATION COMMISSION

Signed Richard W. Lacey (TECHNICIAN)

DATE 4-19-83

APR 07 1983

FORM CP-2/3 Rev. 9-82

INV. NO. 4055-W

CONSERVATION DIVISION Wichita, Kansas



TXO Production Corp.
200 W. DOUGLAS, SUITE 300
WICHITA, KANSAS 67202

April 4, 1983

RELEASE OF WELL INFORMATION

TXO PRODUCTION CORP.
#2 Clarke "J"
SW SW SE, 330' FSL & 2385' FEL
Section 24-31S-13W
Barber County, Kansas
Field: Stonestreet

Spud: 3-26-83
Elev: 1573' K.B.
Geologist: Earl Moore
Contractor: FWA, Rig #32
Surface: 8-5/8" @ 328' w/300 sxs

Ran O.H. Logs

No DSTs.

LOG TOPS

Herington	1818	-245
Cottonwood	2339	-766
Onaga Sh	2597	-1024
Indian Cave	2604	-1031
Wabaunsee	2656	-1083
Tarkio	2851	-1278
Topeka	3314	-1741
U. Douglas	3570	-1997
Lansing	3695	-2122
RTD	3750	
LTD	3743	

D & A, final report, 4-2-83.

Respectfully submitted,

TXO PRODUCTION CORP.

Harold R. Trapp

Harold R. Trapp
District Geologist

/bh RECEIVED
STATE CORPORATION COMMISSION

APR 06 1983
CONSERVATION DIVISION
Wichita, Kansas

Date: 3-26-83
Customer Order No.:
Site: T.X.O.
Top: 7.W.A. 206
Range: Rig #32
Truck Called Out: 11:30am
On Location: 1:30pm
Job Starts: 3:50pm
Job Completed: 4:15pm
Charge To: T.X.O.

Well No. and Part: CLARK J #2
Place: 7 1/2 W. 20th on Loc 206
County: RABBIT (067)
State: KANSAS
Depth of Well: 335'
Depth of Job: 329'
Casing: 8 1/2" ID
Weight: 24#
Size of Hole: 12 1/4"
Ann. and End of Cement: 300' Bulk
Cement Left in Casing by: 20
Kind of Job: SURFACE CASING
Condition of Well at time of Cementing: NORMAL RETURNS
Type of Plug: Wooden Rubber Cap

Pressure Cementing: Minimum Maximum
Time Required Mixing Cement: Minimum Maximum
Time Required Making Cement: Minimum Maximum

Prior Reference to: 2
Price of Job: \$381.82
Second Stage:
Specialty Tools:
Other Charges:
Pump Truck Mileage: \$13.00

Run 8 1/2" casing to 329' cemented with 200 sacks Lite-Weight 38 A-7 followed with 100 sacks Class A. 206 38 A-7 Pump Plug to 309' with fresh water.

CEMENT DID CIRCULATE!
THANKS

Contractor: Dale Walton
Company: 8 1/2 P.C. / MANIFOLD
Address: Medicine Lodge, KANSAS
The above job was done under supervision of the contractor, or his agent whose signature appears below.
Name of Contractor in Location: Yes No
Prices Subject to Correction.

SALES TICKET FOR MATERIALS

QUANTITY SACKS	BRAND AND TYPE	PRICE	TOTAL
200	Lite-Weight	4.30 per ft.	860.00
100	Class A	5.00 per ft.	500.00
77	8 1/2"	.21 lb	170.1
188		6.75 per sack	12.69
1-8 1/2"	WOODEN - Rubber Cap	40.00 per	40.00
		.92 per ft	276.00
		68 per sack	85.68
		56 per sack	56.00
			2,395.86

Delivered by Truck No. T-42
Company from Medicine Lodge
Signature of Operator: Ricky Freeman