

1 040445

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 8/6/84

SE SE SE, SEC. 21, T 31 S, R 13 WXE

330 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name Parr Well # 3-B

Operator: Beren Corporation

County Barber 155.68

Name & Address Box 723

Well Total Depth 4790 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 273

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12:30 p.m. Day: 6 Month: 8 Year: 19 90

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4350', PBTD 4299', Perfs at 3386-90'

1st plug sand back to 3336' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Plugging Proposal Received by Dan Goodrow AUG - 9 1990

(TECHNICIAN) 8-9-90
CONSERVATION DIVISION
WICHITA, KANSAS

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 6 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3336' and dumped 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Maximum pressure 850 psi and shut in 650 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2400' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (If applicable, observe this plugging.)

DATE: AUG 23 1990

INV. NO. 29004

Signed Stephen J. Puffer
(TECHNICIAN)