

1 030367

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,993-00-00

SE NW NW, SEC. 20, T 31 S, R 13

4290 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Hartley "C" Well # 1

Operator: TXO Production Corp.

County Barber 124.80

Name & Address 200 West Douglas, Suite 300

Well Total Depth 3840 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor FWA Drilling Co., Inc. License Number 6165

Address Wichita, KS 67202 (P. O. Box 970, Yukon, OK 73099)

Company to plug at: Hour: 8:00 am Day: 23 Month: January Year: 19 85

Plugging proposal received from Gerald Veatch

(company name) TXO (phone) 316-265-9441

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 660' with 50 sx cement

2nd plug at 390' with 40 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:00 am Day: 23 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 660' with 50 sx cement; 2nd plug at 390' with 40 sx

cement, 3rd & 4th plugs - solid bridge- hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate

mouse hole with 10 sx cement.

STATE CORPORATION COMMISSION

JAN 30 1985

1-30-85  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(If additional description is necessary, use BACK of this form.)

INVOICED

(check diagonal) observe this plugging.

DATE 1-31-85

Signed Steve Durrant  
(TECHNICIAN)

INV. NO. 6788

1-27

FEB 27 1985