

To: 1 090710
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 007-22,508 -00-00
N/2 NE NE, SEC. 20, T 31 S, R 13 W/E
4950 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

7-23

Operator License # 9408
Operator: Trans Pacific Oil Corporation
Name: _____
Address: 100 N. Main, Ste. 1000
Wichita, KS 67202

Lease Name Hartley Well # 1-20
County Barber 149.72
Well Total Depth 4607 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 318

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Co., Inc. License Number 5123
Address 110 N. Market, Ste. 205, Wichita, KS 67202

Company to plug at: Hour: 4 a.m. Day: 23 Month: 7 Year: 19 96

Plugging proposal received from Doyle Folkerts
(company name) Pickrell Drilling Co., Inc. (phone) 316-262-8427

Work: to fill hole with heavy mud and spot cement through drill pipe Base Anhydrite 600'
1st plug at 4600' with 50 sx cement, 2nd plug at 600' with 50 sx cement,
3rd plug at 340' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9 a.m. Day: 23 Month: 7 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 4600' with 50 sx cement,
2nd plug at 600' with 50 sx cement,
3rd plug at 340' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 24 1996
7-24-96
CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE JUL 26 1996
INV. NO. 46132

Signed _____
(TECHNICIAN)