

1 060952

APR 24 1987 15-007-21917-00-00

157 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- N/A

NW NW NE, SEC. 36, T 31 S, R 13 W/E  
4950 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4964

Lease Name Simpson Well # A-1

Operator: DCF Exploration

County Barber 136.57

Name & Address 405 East Ponderosa Drive, Suite 1  
Parker, CO 80134

Well Total Depth 4202 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 365

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 24 Month: 4 Year: 19 87

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4201' PBSD 4173' Perfs at 4175-6, 4163' Elevation 1511'

1st plug sand back to 4100' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11 a.m. Day: 24 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4100' and dump 4 sx cement on top of sand through bailer.

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Maximum pressure 600 psi and shut in 500 psi.

Remarks: Recovered 3470' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by B.J. Titan.  
(If additional space is necessary, use BACK of this form.)

INVOICED

APR 28 1987

Signed Paul A. Luthi (TECHNICIAN)

DATE 4-29-87

CONSERVATION DIVISION  
Wichita, Kansas

INV. NO. 116668