

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

2-010180

API Number: 15-077-21,355-00-00

SE SE SECTION 13 TWP 32 RANGE 08W

OPERATOR LICENSE #30357  
OPERATOR MKJ OIL COMPANY, LLC  
NAME & ADDRESS 705 E 9TH HARPER, KS 67058

660 FEET FROM S SECTION LINE  
660 FEET FROM E SECTION LINE

LEASE NAME NAFFZIGER #1  
COUNTY HARPER  
WELL TOTAL DEPTH 4960' 161.20  
PIPE  
SURFACE CASING 8 5/8" @ 255'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_ X \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: DUKE DRILLING CO., INC.

ADDRESS: P.O. BOX 823, GREAT BEND, KS 67530 LICENSE: 5929

COMPANY TO PLUG AT: HOUR: 16:45 DAY: 4 MONTH: 7 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: MARLAND E. BERGMAN

COMPANY NAME: MKJ OIL COMPANY LLC PHONE: (316) 896-2333

WERE: FILL HOLE WITH HEAVY MUD AND SPOT PLUGS THROUGH DRILL PIPE. SPOT 35 SACKS CEMENT @ 850', 35 SACKS CEMENT @ 300', 25 SACKS CEMENT @ 60', AND FILL RAT HOLE WITH 15 SACKS CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 03 1998

CONSERVATION DIVISION  
WICHITA, KS

PLUGGING PROPOSAL RECEIVED BY: MICHAEL WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL \_\_\_\_\_ PART \_\_\_\_\_ NONE X

COMPLETED: HOUR: 19:30 DAY: 4 MONTH: 7 YEAR: 1998

ACTUAL PLUGGING REPORT: FILLED HOLE WITH HEAVY MUD AND SPOTTED PLUGS THROUGH DRILL PIPE. SPOTTED 35 SACKS CEMENT @ 1300', 35 SACKS CEMENT @ 850', 35 SACKS CEMENT @ 300', 25 SACKS CEMENT @ 60' AND FILLED RATHOLE WITH 15 SACKS CEMENT.

REMARKS: USED 60/40 POZ WITH 4% GEL BY ALLIED. INVOICE #3671.

I DID NOT OBSERVE THIS PLUGGING.

*Michael Wilson*  
MICHAEL WILSON

FORM CP-2/3  
REV. 3/90

11-4-98  
260258