

1 080470

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION W/2 SE NW NE, SEC. 11, T 32 S, R 12
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,354-00-00
4290 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5151
Operator: Gear Petroleum Co., Inc.
Name & Address: 300 Sutton Place
Wichita, KS 67202

Lease Name Frederick Well # 1
County Barber 140.08
Well Total Depth 4310 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 388

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 7 Month: January Year: 19 86

Plugging proposal received from Vernon Duntz
(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4308' PBD 4298' Perfs at 4239-54'; 4272-78'

1st plug pump 1 sack hulls and 20 sx cement to bottom and stop plug at 4150'

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Jack L. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00 pm Day: 7 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 20 sx cement to bottom and stopped plug at 4150', 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

Maximum pressure 900 psi and shut in 800 psi

Remarks: Recovered 3100' 4 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 14 1986

INV. NO. 12032

JAN 13 1986
1-13-86
CONSERVATION DIVISION
Wichita, Kansas

Signed J. A. [Signature]
(TECHNICIAN)