

1080155

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,751-00-00
NE SE NW, SEC. 24, T 32 S, R 12
1650 feet from ~~NXX~~ section line

TECHNICIAN'S PLUGGING REPORT

2310 feet from ~~WXX~~ section line
Krehbiel-

Operator License # 8653

Lease Name Jacobs Well # 24-1

Operator: Petroleum Technologies, Inc.

County Barber

Name & Address

4005 East Kellogg

Well Total Depth 4725 153.56 feet

Wichita, KS 67218

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 348

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Aldebaran Drilling License Number 5829

Address 453 South Webb Road, # 100, Wichita, KS 67207

Company to plug at: Hour: 10:00 am Day: 29 Month: May Year: 19 84

Plugging proposal received from Larry Harris

(company name) Aldebaran (phone) 316-672-7471

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1200' with 50 sx cement

2nd plug at 400' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by J. A. [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:15 pm Day: 29 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1200' with 50 sx cement, 2nd plug at 400' with 50

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate

mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 07 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun
(If additional description is necessary, use BACK of this form.)
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(did not) observe this plugging.

DATE 7-8-84

Signed J. A. [Signature]
(TECHNICIAN)

INV. NO. 1928