

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21325-00-00
Spot: NENENW Sec/Twnshp/Rge: 22-32S-12W
330 feet from N Section Line, 2310 feet from W Section Line
Lease/Unit Name: LONKER - C Well Number: 1
County: BARBER Total Vertical Depth: 4817 feet

Operator License No.: 31252
Op Name: TINDALL OPERATING COMPANY
Address: 12741 EAST CALEY, STE. 142
ENGLEWOOD, CO 80111

Conductor Pipe: Size feet: 8156.53
Surface Casing: Size 8.625 feet: 366 WITH 200 SX CMT
Production: Size 5.5 feet: 4817 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/15/2001 9:30 AM
Plug Co. License No.: 31252 Plug Co. Name: TINDALL OPERATING COMPANY
Proposal Rcvd. from: RON MOLZ Company: TINDALL OPERATING Phone: (620) 886-2140

Proposed Plugging Method: SET CIBP @ 4700' & 2 SX CMT. PERFORATE 5 1/2" CASING AT 600'. CIRCULATE CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/15/2001 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4780'. PERFS AT 4721-25 & 4728-30'. SET CIBP @ 4625' & PUT 2 SX CMT ON TOP OF CIBP WITH DUMP BAILER. PERFORATED 5 1/2" CASING AT 600'. PUMPED DOWN 5 1/2" CASING WITH 178 SX CMT. CEMENT DID CIRCULATE UP 5 1/2" X 8 5/8" ANNULUS.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED

DEC 07 2001

KCC WICHITA

INVOICED

DATE 12-10-01

INV. NO. 2002061050

NOV 19 2001

Form CR-23

MP