

To: 1 040277

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

5-23  
API NUMBER 15- 007-01,025 -00-01

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 26 1989

TECHNICIAN'S PLUGGING REPORT

Operator License # 4581  
Operator: EXOK, Inc.  
Name & Address: 6410 B. North Santa Fe  
Oklahoma City, OK 73116

CONSERVATION DIVISION  
Wichita, Kansas

2310 feet from S section line  
4950 feet from E section line  
Lease Name Kirkbride Well # 1  
County Barber  
Well Total Depth 1899 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
never produced  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Hayes Well Service License Number 5429

Address P.O. Box 108, Attica, KS 67009

Company to plug at: Hour: 3 p.m. Day: 23 Month: 5 Year: 19 89

Plugging proposal received from Carl Durr  
(company name) EXOK (phone) 316-478-2890

were: 5 1/2" at 4472' Open hole 4472-78' Elevation 1577' GL  
This was a washdown attempt which was abandoned on 5/17/89. They reached a total depth of 1899' and ran into junk in hole (wood, gunny sacks, rope, iron).  
1st plug pump down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 3:45 p.m. Day: 23 Month: 5 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.  
Maximum pressure 900 psi and shut in 375 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-26-89

INV. NO. 25934  
5-23

Signed Stephen J. Pfeifer  
(TECHNICIAN)