

1 040838

4-21

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

APR. NUMBER 15-007-21,518-0000
100' E of
NW NE NE, SEC. 21, 7 32 S, R 12 W/8
4950 feet from S section line
890 feet from E section line
Lease Name Snyder Well # 2
County Barber
Well Total Depth 4900 159.25 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 401

TECHNICIAN'S PLUGGING REPORT

Operator License # 5399

Operator: American Energies Corporation
Name & Address 155 N. Market Ste. 710
Wichita, KS 67202

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor VAL Energy, Inc. License Number 5822

Address P.O. Box 322, Haysville, KS 67060

Company to plug at: Hour: 4 p.m. Day: 21 Month: 4 Year: 19 94

Plugging proposal received from Curtis Ledbetter

(company name) VAL Energy, Inc. (phone) 316-522-1560

logs: 4 1/2" at 4887' w/150 sx cement, PBSD 4862', Perfs at 4796-4800'

1st plug sand back to 4745' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 21 Month: 4 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4745' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 1000 psi and shut in 600 psi.

RECEIVED STATE CORPORATION COMMISSION

APR 27 1994

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3520' of 4 1/2" casing (if additional description is necessary, use BACK of this report.)

observe this plugging.

DATE 4-29-94

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 40362