

1 040839

4-21

API NUMBER 15-007-21,463-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
260 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NE NE, SEC. 21, 7 32 S, R 12 W/8  
4950 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5399

Lease Name Snyder Well # 1

Operator: American Energies Corporation

County Barber

Name & Address 155 N. Market, Ste. 710

Well Total Depth 4872 158,34 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 434

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor VAL Energy, Inc. License Number 5822

Address P.O. Box 322, Haysville, KS

Company to plug at: Hour: 2:30 p.m. Day: 21 Month: 4 Year: 19 94

Plugging proposal received from Curtis Ledbetter

(company name) VAL Energy, Inc. (phone) 316-522-1560

vars: 4 1/2" at 4870' w/175 sx cement, PBD 4850', Perfs at 4786-94'

1st plug sand back to 4735' and dump 4 sx cement on top of sand bridge through bailer,

2nd plug pump down 8 5/8" surface pipe with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel,

1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 p.m. Day: 21 Month: 4 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4735' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50' sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Maximum pressure 900 psi and shut in 550 psi.

Couldn't get plug container in-pumped through swedge.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3435' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION APR 27 1994

INVOICED

observe this plugging.

DATE 4-29-94

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 40363