

1040958 4-27

API NUMBER 15- 007-21,383-00-00

STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

SE SE NE, SEC. 16, T 32 S, R 12 W/E
2970 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3399
Operator: Farrar Pump & Supply Co.
Name:
Address: P.O. Box 209
Medicine Lodge, KS 67104

Lease Name Eby Well # 1
County Barber 160.23
Well Total Depth 4930 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 401

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Val Energy, Inc. License Number 5822
Address: P.O. Box 322, Haysville, KS 67060

Company to plug at: Hour: 10:15 a.m. Day: 27 Month: 4 Year: 1995

Plugging proposal received from Mike Farrar
(company name) Farrar Pump & Supply Co. (phone) 316-886-3763

work: 4 1/2" at 4930' w/75 sx cement, PBD 4500', Perfs at 4428-32'
1st plug sand back to 4375' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 27 Month: 4 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4375' and dumped 4 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls and 100 sx cement. Maximum pressure 750 psi and shut in 700 psi.
Threads in 8 5/8" collar bad. "Plated 8 5/8"-no wiper plug. After pumping 300# of hulls and
10 sx gel, 8 5/8" surface pipe split (blew out-600#). Back hoe dug out pipe-thin where split-
cut surface pipe off and replated.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2550' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

1 (do not check) observe this plugging.

INVOICED
DATE 5-2-95
INV. NO. 42726

Signed Stephen J. [Signature]
(TECHNICIAN)