

To: 1 041141
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

1-23

API NUMBER 15-007-20,459-00-00
100' ENE of
SE SW SW SEC. 14, T 32 S, R 12 W/E
495 feet from S section line
4025 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3399
Operator: Farrar Pump & Supply Co., Inc.
Name & Address: P.O. Box 209
Medicine Lodge, KS 67104

Lease Name Vanderwork Well # 1
County Barber 152.43
Well Total Depth 4690 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 497

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 2:30 p.m. Day: 23 Month: 1 Year: 19 96

Plugging proposal received from Paul Shelite
(company name) Farrar Pump & Supply Co., Inc. (phone) 316-886-3763

5 1/2" at 4683' w/150 sx cement, PBTD 4150', Perfs at 4112-16, 4116-22'
1st plug sand back to 4050' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 23 Month: 1 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4050' and dumped 5 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 1000 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2483.65' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED
DATE 1-20-96
INV. NO. 44750
1-23

Signed Stephen J. Puffer (TECHNICIAN)

RECEIVED
KANSAS CORP COM
1996 JAN 26 10:24 AM